BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/03/2014-15, Date:31.10.2014.

**ITEM NO: 66**

**SCHEDULE-B**

**NAME OF WORK:** Improvements & Construction of CC road, drain & RCC Culverts at Coconut Garden (Sharada School road) 2nd, 3rd, 4th & 5th cross road in Dasarahalli Ward No 15.

| Sl. No | Description of work | Unit | Qty | Rates Quoted by Contractor **A PRADEEP** | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications Complete as per specification and direction of Engineer-in-charge of the work. | Cum | 136.15 | 95.0 | Rupees Ninety Five Only |
| 2 | Removing B.S.Slab of drain and stacking etc., Complete as per specification and direction of Engineer-in-charge of the work. | Sqm | 718.2 | 50.0 | Rupees Fifty Only |
| 3 | Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work. | Cum | 68.07 | 4601.0 | Rupees Four Thousand Six Hundred One Only |
| 4 | Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work. | Cum | 81.54 | 5200.0 | Rupees Five Thousand Two Hundred Only |
| 5 | Refixing stone slabs of drains and pointing in CM 1:3 etc., Complete as per specification and direction of Engineer-in-charge of the work. | Sqm | 430.92 | 70.0 | Rupees Seventy Only |
| 6 | Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete as per specification and direction of Engineer-in-charge of the work. | Sqm | 287.28 | 620.0 | Rupees Six Hundred Twenty Only |

Signature of the Contractor

Executive Engine

| | | | | | |
|---|---|---|---|---|---|
| 7 | Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing Complete as per specification and direction of Engineer-in-charge of the work. | Sqm | 179.55 | 950.0 | Rupees Nine Hundred Fifty Only |
| 8 | Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. Complete as per specification and direction of Engineer-in-charge of the work. | Sqm | 448.88 | 1572.0 | Rupees One Thousand Five Hundred Seventy Two Only |
| 9 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work. | Cum | 136.15 | 70.0 | Rupees Seventy Only |

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,